



**ALAN ROBINSON**

**CONSULTING CIVIL & GEOTECHNICAL ENGINEERS**



**ESKOM HENDRINA POWER STATION**

**PRELIMINARY DESIGN REPORT**

**PROPOSED WET ASH DISPOSAL FACILITY (ADF)  
WITH ASH WATER RETURN DAMS (AWR'S)**

**REV 6**

**Ref 618PD. Rev 6**  
**Date: 17 February 2015**  
**Fax : 0866 89 46 57**  
**Cell: 0826 10 12 23**  
**www.alanrobinson.co.za**

**ALAN ROBINSON Pr Eng ECSA 750 693**  
BSc/Civil (Wits); GDE; ECSA, CESA (past member)  
**CIVIL & GEOTECHNICAL ENGINEERS**  
**P O BOX 2861**  
**NORTHCLIFF**  
**2115**



**ESKOM HENDRINA POWER STATION**  
**PRELIMINARY DESIGN REPORT**  
**PROPOSED ADF WITH AWRD'S**

**REV 6**

CONTENTS

	<u>Page No.</u>
EXECUTIVE SUMMARY	3
1. SCOPE OF WORK	4
2. SITE SELECTION AND SIZING	4
3. DESIGN ASSUMPTIONS	4
4. ASH DISPOSAL	5
4.1 Production Rates	5
4.2 Construction of the disposal facility	5
4.3 Stability and Rate of Rise	6
5. HYDROLOGY AND WATER BALANCE	7
6. DESIGN OF ASH DISPOSAL FACILITIES	7
6.1 Seepage Control	7
6.2 Stormwater Control	8
6.3 Capping/rehabilitation	8
7. ASH WATER RETURN DAMS (AWRD's)	8
8. CAPEX COSTING	9
9. RISK EVALUATION	10
9.1 Geotechnical Conditions	10
9.2 Residue Characterisation	10
9.3 Chemical Profile	11
9.4 Safety Classification	12
10. REHABILITATION	12
APPENDIX A: DRAWINGS	13
APPENDIX B: WATER BALANCE	14
APPENDIX C : BUDGET COSTING	15
APPENDIX D : STABILTY AND RATE OF RISE	16

**ESKOM HENDRINA POWER STATION  
PRELIMINARY DESIGN REPORT  
PROPOSED ASH ADF, WITH AWRD'S**

**REV 6**

**EXECUTIVE SUMMARY**

A Preliminary Design has been carried out on the selected Site E which is able to accommodate 43 million m<sup>3</sup> of ash from the Hendrina Power Station. The purpose of this report is to provide preliminary design information for the wet ash disposal facilities, and associated pollution control structures for the remaining 17 years of the operational life of the Hendrina Power Station, until July 2035.

This report specifically covers the preliminary design of Ash disposal facility on Site E, with AWRD'S and associated storm water control measures, taking into consideration the topographical and physical constraints. For the purpose of this project, the Ash has been classified as Type 3 Waste, requiring a Class C landfill barrier system.

Because of the possibility of seepage occurring into the subsoils beneath the disposal area, a single Class C composite barrier, and HDPE liner will be provided to control the leachate, which will then be led into the AWRD's, via a solution trench, and then be pumped back to the station for reuse.

The Class C barrier design should incorporate a drainage layer on top of the barrier system containing drainage pipes of adequate size, spacing and strength to ensure atmospheric pressure within the drainage application for the service life of the ash disposal facility as per the DEA's National Norms and Standards.

Unfortunately, in view of the limited extent of this site it is not possible to phase the construction of the ADF. The Area to the East of the Dam has been "ear-marked" for topsoil and subsoil stockpiling.

As part of the stormwater control measures on the site, two pollution control dams (AWRD's) are planned to cater for the facility, and will be integrated into the existing system, by means of pressure pipelines. The AWRD's will be lined with a composite Class C barrier, comprising a 2,0 mm HDPE, to arrest seepage. The dams have been sized to contain all stormwater runoff, such that they do not spill into a clean water system more, than once in fifty years on average.

Also in terms of GN704, all clean and dirty water separation is enforced, and all channels are required to convey the 50-year flood peak.

The water accumulated in AWRD should never be more than 10 to 15% of its capacity, at any time, to minimise the likelihood of spilling during a storm event.

Some of the test holes encountered a perched aquifer above a ferricrete layer, and more boreholes will be need to fully understand the aquifer characteristics of the site, both shallow and at depth.

A more detailed cost estimate for the infrastructure will be prepared at Tender stage. Some indication of the expected construction costs for the various facilities related to the ash disposal. Appendix C contains the costing estimate as at July 2013.

**ESKOM HENDRINA  
PRELIMINARY DESIGN REPORT  
PROPOSED ASH DISPOSAL FACILITY AT SITE E WITH AWRD'S**

## 1. SCOPE OF WORK

A Preliminary Design has been carried out on the selected Site E which is able to accommodate 43 million m<sup>3</sup> of ash from the Hendrina Power Station.

The purpose of this report is to provide preliminary design information for the ash disposal facility at site facilities for the ash facilities and associated pollution control structures for the remaining 17 years of the operational life of the Power Station, until July 2035.

## 2. SITE SELECTION AND SIZING

The rationale for the selection of the location of the ash disposal facility is as follows:

- DMR is currently busy with a prospecting application on the preferred alternative, and Eskom is in the process of objecting to this. **Verification of mining rights does not form part of the scope of this report.**
- The areas are in close proximity to the existing Power Station, as defined by the station's technical requirements/criteria.
- The topography is acceptable in terms of surface gradients to accommodate pollution control measures
- The area is unaffected by sensitive or pristine wet lands and associated flood plains.

## 3. DESIGN ASSUMPTIONS

The design assumptions used, are given below, with the following comments:

a) The maximum ADF height is subject to review once the final Geotechnical investigation has been carried out. The factor of safety given below, will be the minimum allowable, and will be determined from soil and topographical conditions. These will be verified at Detailed Design Stage.

b) Design Parameters (\* to be verified)

- Average ADF side Slope	1:3 to 4
- Storm Design Criteria	GN704
- Min. factor of safety	1,5
- Pool free board (m)	0,8m
- Ash Bulk Density (t/m <sup>3</sup> )	1,4 (measured)
- Dry density of ash (t/m <sup>3</sup> )	1,0 *
- ADF Capacity	43,5 x 10 <sup>6</sup> m <sup>3</sup>
- Ash production	30,7% *
- Ash SG	2,36
- Maximum rate of rise	3,5m/year
- Ash Permeability	5m/year (1,6 No <sup>-7</sup> m/sec) *

## 4. ASH DISPOSAL

For the purposes of this project, the Ash has been classified as a Type 3 Waste requiring a Class C landfill barrier system. The ash disposal area comprises various components and the layout is shown on the drawings as:

- Two pollution control dams (AWRD's)
- Wet Ash Disposal facility
- Clean water diversion trench/bund walls
- Dirty water drains/leachate interception and collection systems
- Penstock and outlet pipelines
- Silt Trap

### 4.1 Production Rates

The expected Ash production is 40 million m<sup>3</sup> of ash, over the remaining 17 years, based on the most recent estimate, provided by Eskom.

### 4.2 Construction of the disposal facility

In summary, the following construction phases are envisaged :

Phase 0	Relocate water mains and power lines.
Phase I	Remove topsoil and subsoil to a depth of 600 mm, and stockpile separately
Phase II	Earthworks to cut and fill in situ material, to form the platform within the footprint for the dam.
Phase III	Construct penstock and clean and dirty water drains.
Phase IV	Place and weld 1,5mm HDPE “embossed” liner and other layers, as detailed to levels and grades, to form a Class C composite barrier.
Phase V	Construct starter wall to accommodate initial rate of rise.
Phase VI	Deposit ash as detailed below, and on the drawings.

The ring dyke or paddock systems will be used to construct the ADF as follows:

The impoundment wall, or daywall, is formed by a perimeter outer paddock wall and a parallel inner paddock wall. These walls are constructed between 30 m and 60 m apart, and are formed into paddocks by the construction of perpendicular ash cross walls. The water pond lies within the daywall in the night paddock.

The ash deposited in these paddocks comprises about 80% fly ash and 20% coarse or bottom ash. The ash is mixed with water, and pumped at a water to solids ratio of 1:5 by mass, for both fly ash and coarse or bottom ash. The ash is then pumped, via a ring

main, as a slurry to the ADF complex through large steel pipes. Only fly ash is used for wall construction (daywalls), while coarse or bottom ash or fly ash is deposited in the inner portion or night paddock of the ADF.

Vibrating wire electronic Piezometers, should be installed just before Ash deposition and extended as the level rises, to monitor porewater pressure levels, for stability evaluation in critical areas. The positions will be determined at the detailed design stage, based on the underlying soils and stability analysis.

#### 4.3 Stability and Rate of Rise

The maximum height of the ADF is 61m ie 1688m above MSL.

In order to accommodate the initial rate of rise a 16,5m high starter wall to elevation of 1644m is required. Towards the end of life, the R.O.R rises to 3,5. The expected rate of rise has been plotted and presented in Appendix D.

The Stability of ADF E has been assessed on the available laboratory test results. The overall side slope is 1:3, but this may need to be “flattened” to provide a suitable Factor of Safety, once the full set of laboratory tests are available. The available tests have provided immediate un-drained shear parameters, and additional testing will be needed to assess long term underlying soil properties, after consolidation.

Indications critical failure surfaces at various sections with the factor of safety for circular and non-circular “failure” modes are given in Appendix D with the phreatic line as shown. The following soil parameters were used in the analysis.

		<b>C'</b> <b>(kPa)</b>	<b>Ø'</b> <b>(deg)</b>	<b>Density</b> <b>(kN/m<sup>3</sup>)</b>
Ash	Day Wall	5*	35*	1,4*
	Inner	0*	35*	1,4*
A4/HDPE (interface)		0*	22*	1,0*
Fill Platform		40*	30*	2,0*
Shallow (Poor)	Soil	18*	26*	2,0*
Deeper	Soil	150*	35*	2,0*

\* These figures to be verified by additional testing, taking the liner into account.

The sections analysed are as follows :

	<b>FOS Circular</b>	<b>FOS Wedge</b>
Section 1 at D7	1,93	1,88
Section 2 at D18	1,69	2,02
Section 3 at D21	2,75	2,67
Section 4 at D14	2,41	2,51

As can be seen from the figures above, the Dam is stable at a 1:3 average side slope, with the assumed soil parameters, and effective toe draining in place.

The factor of safety can be improved by removing areas of soft clay, if needed, and replacing it with selected compacted material of at least G8 quality.

**The stability of ADF needs to be re-assessed at detail design stage, in conjunction with the proposed HDPE liner, and its interaction with the insitu soils.**

## 5. HYDROLOGY & WATER BALANCE

The site is not affected by floodlines and all drains and AWRD's will be sized in terms of the criteria set out in the ILANDA Water Services Report, which will be issued under separate cover.

The water balance has been carried out to assess the water utilisation, and to size the AWRD's. The interaction of the proposed ash disposal areas with this resource has been given in the ILANDA Report, in Appendix B.

## 6. DESIGN OF ASH DISPOSAL FACILITY

### 6.1 Seepage Control

Because of the possibility of seepage occurring into the subsoils beneath the disposal area, a Class C composite barrier, and HDPE liner will be provided to control the leachate, which will then be led into the AWRD's, via a solution trench and will then be pumped back to the station for reuse.

The Class C barrier design should incorporate a drainage layer on top of the barrier system containing drainage pipes of adequate size, spacing and strength to ensure atmospheric pressure within the drainage application for the service life of the ash disposal facility as per the DEA's National Norms and Standards.

Some of the test holes encountered perched aquifer above a ferricrete layer and more boreholes will be need to fully understand the aquifer characteristics at depth, so in the case of the ADF, a 1,5mm embossed or co-extruded HDPE, with suitable frictional properties must be used.

## 6.2 Stormwater Control

As shown on the drawings the open drains and berms separate the “clean” water runoff, from the “dirty” water, to divert clean run-off around the AWRD’s and ADF.

The AWRD’s have been sized to collect the dirty water via the penstock from the “top” of the ADF. The water from the sides of the ADF and solution trenches will be directed into a separate compartment in the AWRD, as clear water.

The solution trenches will be lined with concrete.

## 6.3 Capping/rehabilitation

The Contractor shall, in accordance with the requirements of the Operations and Maintenance Manual be responsible for the:

- Gradual stripping and stockpiling of topsoil
- Gradual shaping of side slopes and top of the ADF
- Gradual spreading of topsoil to cover shaped ADF side slopes and top surface
- Planting of grass for erosion control on prepared slopes
- Establishment of veld grass on the prepared areas
- Establishment of indigenous trees and shrubs
- Aftercare of rehabilitated areas to ensure continued stability and eventual self sustainability
- The upkeep of a complete rehabilitation progress manual.

## 7. ASH WATER RETURN DAMS (AWRD’S)

All the dirty water run-off which accumulates on top of the ADF will find its way into one of the AWRD’s. Water from the sides and seepage collection drains will be routed to a separate compartment in the AWRD, as “clear” water.

The ash return dams perform the following functions, in conjunction with the silt trap :

- a) They provide a facility for settling out the very fine material which does not settle out on the ADF.
- b) They provide short term emergency storage capacity for stormwater from



the ADF.

The AWRD's will be used in conjunction with temporary storage on top of the ADF for periods of up to three days, until it is taken up in the normal ashing cycle. In addition, excess polluted stormwater can only be stored on top of the ADF if it has sufficient freeboard.

None of the AWRD's available capacities may fall below 75% of the total capacity of the dam as a result of the ash settlement. Should the total capacity of an AWRD be reduced to 75% of the total capacity by silting, the settled ash must be dredged or cleaned from the bottom of the dam so as to return the dam to its correct capacity, and so not to affect the integrity of the ash disposal facility.

Spillways will be provided for from each dam, to cater for the unlikely event of an overflow occurring.

The storage facilities will be formed by excavating into the virgin subsoils or importing fill from within the site, to create the required capacity, in a "cut and fill" operation, taking the ground water table level into account.

Two AWRD's and a silt trap are proposed, for the Ash disposal facility, details of which are shown on the drawings.

The AWRD's will be lined with a composite Class C type barrier, comprising a 2,0 mm HDPE liner with compacted clay layers, to arrest seepage. The dams have been sized to contain all stormwater runoff, such that they do not spill more than once in fifty years on average.

In terms of GN704, all clean and dirty water separation is enforced, and all channels are required to convey the 50-year flood peak.

The Report by ILANDA Water Services provides details of the design criteria and assumptions made.

## **8. CAPEX COSTING**

A more detailed cost estimate for the various components of the infrastructure, will form part of the Tender Design stage. Indicative costs are given in Appendix C, and the estimate figures based on current rates are including VAT and 2,5% contingencies are:

ADF E

R354 million\*

AWRD's (East & West)

R27,1 million\*

This translates to R8,86 per m<sup>3</sup> of dry ash deposited, as at July 2013.

## 9. RISK EVALUATION

The following risks will be taken into account during the next phase of the design:

- 9.1 Geotechnical Conditions – the maximum ADF height and side slope will be reviewed, based on the actual soil properties, once these are to hand.

Boreholes and possibly Geophysical studies will also be needed to fully understand the Geohydrological conditions, together with the location and type of aquifers beneath the ADF.

A number of test holes and DPSH tests have been carried out, and the results with an evaluation of the site, is covered in a separate Geotechnical Report to be issued shortly.

The areas of perched water Table and poorer soils, based on the test hole logs and DPSH tests, generally correlate with the areas which are not cultivated, and highlighted on the Google Earth Image.

Generally the soils are poorer along the Eastern and North Eastern boundaries of the proposed ADF.

- 9.2 Residue Characterisation – in terms of the DEA's National Norms of 2013, an Ash Classification was carried out by Jones and Wagner and reported on in their report JW175/14/E699 – Rev 00.

The new waste classification system, which replaced the Department of Water Affairs and Forestry's Minimum Requirements classification system on 23 August 2013, focuses on the long term storage (in excess of 90 days) and disposal of waste on land or waste disposal facilities. The system is based on the Australian State of Victoria's waste classification system for disposal, which using the Australian Standard Leaching Procedure (ASLP) to determine the leachable concentrations (LCs) or pollutants (DEA, 2013a).

- a) The Ash has been characterised to identify any potential significant health and safety hazards together with environmental impact that may be associated with the residue being stockpiled.
- b) The residue deposits have been characterised in terms of their physical

characteristics including size, distribution, permeability, void ratios, strength, SG and water content.

- c) The chemical characteristics which have been identified would include an assessment of the propensity to oxidise or undergo spontaneous combustion. The PH and chemical composition of the leachate water would also be assessed.

The ash seepage water reporting to the base of the ash disposal facility represents the actual threat to the receiving environment, especially the surface and groundwater. The ash seepage water was assessed as a Type 3 waste. The chemical constituents resulting in this outcome are aluminium, boron, TDS and sulphate are given in Table 3-3 of the J&W Report.

### 9.3 Chemical Profile

The following is an extract from the J&W report :

“Based on the assessment carried out, the ash was assessed as a Type 3 waste requiring disposal on a waste disposal facility with a Class C barrier system. This barrier system is the least conservative composite barrier system currently accepted by the DWS . As the ash seepage water has a low risk of impacting on the groundwater in the area (as was demonstrated by Infotox, Groundwater Sequire and Geostratum in their draft report Health-risk Based Assessment of the Hendrina ADF Expansion Project dated September 2013) (Van Niekerk et al 2013) the installation of a Class C barrier system for the new wet ash disposal facility should be sufficient to protect the environment in the long term. A more conservative barrier system should, however, be considered for the return water dams.

### 9.4 Safety Classification

In terms of safety classification the ash disposal facility will be differentiated between high, medium and low hazard on the basis for the potential to be a risk to life and property.

The SABS 0286/1998 Code will be used to classify the ADF in terms of a prescribed Safety Classification system that differentiates between high, medium and low hazard potential. This classification as well as the completion of the safety questionnaire will be done during the Risk Assessment on the ADF, during detailed design stage.

The initial conclusion is that the ADF has a medium to high Hazard Classification.

## 10. REHABILITATION

Sufficient cover material for the sides and top of the dam will be stockpiled prior to construction from within the “footprint” of the facility.

Once the decommissioning phase is completed, the top of the Dam will be paddocked and covered with 300mm of compacted clayey sub- soil, followed by 200mm of topsoil from the previously stockpiled material.



**AW Robinson Pr Eng**  
BSc/Civil (Wits); GDE; CESA (past member);  
ECSA 750 693

**APPENDIX A  
DRAWINGS**

<b>Drawing No.</b>	<b>Rev.</b>	<b>Title</b>
618/300	A	ADF E test positions
618/305	B	DPSH depth to dense or firm material
618/310	C	Proposed ADF E layout plan
618/320	O	ADF typical details (wall section)
618/332	A	AWRD West and East safety details
618/333	A	AWRD East wall section
618/335	A	AWRD East and West pipe spillways
618/336	A	AWRD East inlet details
618/342	C	AWRD West safety details
618/343	B	AWRD West (clear water) wall section
618/346	A	AWRD West inlet details
618/350	0	Silt trap wall section
618/382	0	HDPE liner details
618/384	0	Standard details Sheet 1
618/386	0	Energy dissipation structure and pipe crossing
618/390	0	ADF standard details (Sheet 1)
618/391	0	ADF standard details (Sheet 2)
618/392	0	ADF standard details (Sheet 3)
618/400	C	ADF and AWRD barrier details
-		Plot of rate of rise





Google earth



**LEGEND**

- TH & DPSH
- DPSH ONLY
- D2 HOLE NO.
- APPROXIMATE POOR SOIL OR PERCHED WATER TABLE BOUNDARY



X 2 881 000  
Y - 60 000

X 2 881 000  
Y - 60 000

X 2 883 000  
Y - 60 000

Metre  
0 100 200 300 400 500  
WGS 29

**ISSUED FOR DISCUSSION PURPOSES ONLY**

No.	Amendments	Appr.	Date
A	DRAWING UPDATED		16/02/15
B	DRAWING CREATED		14/06/13

No.	Checked	Revised	By	Date
	Checked	Checked		
	Drawn	Drawn		
	Deleted	Deleted		

**ECSA 750 693**

By **ALAN ROBINSON**

**ALAN ROBINSON CONSULTANTS**  
 P.O. Box 2861  
 279 Rietbosdam rd  
 WINTERBURG Cell: 082-16-15-29  
 Johannesburg Fax: 082-684-607  
 2115

**LIDWALA**

**HENDRINA POWER STATION**

**WADFE TEST POSITIONS**

Scale: **N.T.S**

Sheet: **1 of 1**

Drawing No: **618/300**

Scale: **N.T.S**

Sheet: **1 of 1**

Drawing No: **618/300**

**LEGEND**

- TH & DPSH
- DPSH ONLY
- HOLE NO.
- APPROXIMATE POOR SOIL OR PERCHED WATER TABLE BOUNDARY
- D1/D1.5 TO DENSE OR FIRM MATERIAL
- 1m CONTOURS
- STABILITY SECTION

**ISSUED FOR DISCUSSION PURPOSES ONLY**

No.	Arrangements	Appr.	Date
B	DRAWING UPDATED		16/02/15
A	DRAWING UPDATED		27/11/14
0	DRAWING CREATED		15/07/13

**ECSA 750 693**

For **ALAN ROBINSON**

**ALAN ROBINSON**  
 CONSULTING ENGINEER  
 P.O. Box 2861  
 279 Bellvue rd  
 MORITJIFF  
 ABANTHUBURG  
 2115

**LIDWALA**



**HENDRINA POWER STATION**

**DPSH DEPTH TO DENSE OR FIRM MATERIAL**

SCALE: **N.T.S**

Sheet 1 of 1

Drawing No. **618/305**





**LEGEND**

	PENSTOCK PIPE
	CLEAN WATER TRENCH
	SOLUTION TRENCH
	CLEAN WATER BERM
	TOE & MAIN DRAIN
	1m CONTOURS
	STARTER WALL

ISSUED FOR DISCUSSION PURPOSES ONLY

No.	Arrangements	Appr.	Date
C	DRAWING UPDATED		16/02/15
B	DRAWING UPDATED		10/04/14
A	QUANTITIES AMENDED		17/07/13
D	DRAWING CREATED		09/07/13

ECSA 750 693  
 ALAN ROBINSON


**ALAN ROBINSON**  
 CONSULTING ENGINEER  
 P.O. Box 2861  
 279 Bellaryreddy rd  
 Abanahlabung 215  
 T: (011) 476-4286  
 Cell: 082-16-12-29  
 Fax: 082-684-607

Client: **LIDWALA**

Project: **HENDRINA POWER STATION**

Description: **PROPOSED WADDF E LAYOUT PLAN**

Scale: **N.T.S**  
 Drawing No: **618/310**  
 SHEET 1 of 10



X 2 881 000  
 Y - 60 000

WEST ARWD  
 31 600 m³  
 (CLEAR WATER)  
 SILT TRAP

PUMPING LINE

WEST ARWD  
 91 400 m³  
 SILT TRAP

RELOCATE POWER LINE

29° 35' 29.82" E  
 26° 2' 39.76" S  
 VOLUME : 43 MILLION m³ ASH  
 AREA : 128 ha  
 MAX HT 1688m

DAME


SILT TRAP

PUMPING LINE

EAST ARWD  
 10 000 m³  
 (CLEAR WATER)

POSSIBLE EXTENSION TO ASH AREA

RELOCATE WATER MAIN  
 TOE DRAIN  
 MAIN DRAIN



X 2 883 000  
 Y - 60 000

ISSUED FOR DISCUSSION PURPOSES ONLY

No.	Amendments	Rev.	Date
0	DRAWING CREATED	1	17/12/21

ECSA 750 693  
ALAN ROBINSON


**ALAN ROBINSON ENGINEERING**  
 CONSULTING ENGINEERS  
 12 Oudewijk, P.O. Box 2961, Tel: (011) 479-4388  
 279 Watermodem rd, Northcliff, Call: 083-10-12-29  
 Johannesburg, Gauteng, South Africa. Fax: 086 864 867

LIDWALA


Project: **ESKOM ASH HENDRINA**

Description: **WADF TYPICAL DETAILS (WALL SECTION)**


Scale: <b>N.T.S</b>	Sheet of: <b>10</b>
Drawing No: <b>618/320</b>	




DETAIL D1 - SECTION THROUGH DAM (DAM UPSTREAM)



DETAIL D2 - SECTION THROUGH DAM (DAM DOWN STREAM)



DUMP 2 - DETAIL S2



DUMP E - DETAIL S1

**LEGEND**

A1 +4.1

SETTING OUT POINTS & DEPTH  
(\* ABOVE / -BELOW G.L.)

NOTE:  
ALL WORKS TO BE DONE  
TO SABS 1200

**TEST HOLE**

- TH1
- LIFE BODY
- UNDERDRAIN (DETAIL V)
- PENSTOCK PIPE
- SOLUTION TRENCH
- HEADWALL

ISSUED FOR DISCUSSION PURPOSES ONLY

No.	Amendments	Appr.	Date
1	DRAWING UPDATED		22/11/24
2	DRAWING CREATED		10/07/23

ECSA 750 693

For ALAN ROBINSON *Alan Robinson*






**MANAGEMENT**  
**CONSTRUCTION**  
**SAFETY**  
**REGISTRATION 1986**  
 P.O. Box 2861 Tel: (011) 479-4266  
 27a Waterlooville rd NORTRICHTERFORD 001-008-10-12-83  
 Johannesburg Fax: 008 004 6507

Client: **LIDWALA**

Project: **ESKOM ASH HENDRINA**

Description: **AWRD EAST SAFETY DETAILS**

SCALE <b>as shown</b>	SHEET OF SHEETS <b>618/332</b>
Drawing No. <b>618/332</b>	



NOTE:  
ALL WORK IS TO BE DONE  
TO SABS 1200

ISSUED FOR  
DISCUSSION PURPOSES  
ONLY

No.	Amendments	Rev.	Date
A	DRAWING UPDATED	2/17/14	
0	DRAWING CREATED	10/07/13	

ECSA 750 693

ALAN ROBINSON P.Eng

**ALAN ROBINSON ENGINEERING**  
P.O. Box 2861 Tel: (011) 479-4266  
27a Waterlooville rd NORTRICHTY Call: 082-10-12-23  
Johannesburg Fax: 086 884 6577


LIDWALA

ESKOM ASH  
HENDRINA

AWRD EAST  
WALL SECTION

SCALE  
N:1S

SHEET 1 OF 1 SHEETS  
Drawing No.  
**618/333**



SECTION B-B

SECTION - AWRD WALL  
(CLEAR WATER)

NOTE:  
70kg SAND FILLED BALLAST BAGS  
PLACED ON 5m GRID ON FLOOR

BARRIER LAYER  
TO DETAIL Q6  
ON DWG 618 / 400

ISSUED FOR DISCUSSION PURPOSES

Revised:	Scale No:	Drawn:	Checked:
Revised:	Scale No:	Drawn:	Checked:
Revised:	Scale No:	Drawn:	Checked:
Revised:	Scale No:	Drawn:	Checked:

ECSA 750 693

For ALAN ROBINSON P.Eng



**ALAN ROBINSON ENGINEERING**  
 12 Ooriview P.O. Box 2861 Tvl (011) 478-4266  
 27a Waterreken rd NORTRICHTER Call: 0828-10-12-23  
 Johannesburg Fax: 086 884 657


LIDWALA

ESKOM ASH HENDRINA


AWRD EAST & WEST PIPE SPILLWAYS

Scale	N:1S
Sheet No	1 OF 3
Drawing No	618/335





**DETAIL P - INLET ( FROM SOLUTION TRENCH ) TO AWRD EAST**



**FRONT VIEW**

ISSUED FOR DISCUSSION PURPOSES

No.	Amendments	Appr.	Date
A	DRAWING UPDATED		27/11/14
0	DRAWING CREATED		10/07/13

Drawn	Checked	Scale

ECSA 750 693

For ALAN ROBINSON P.Eng



12 Oostervue  
27a Waterlooven rd  
NORMANCY  
Johannesburg

Client:

LIDWALA

Project:  
**ESKOM ASH  
HENDRINA**

Description:  
**AWRD EAST  
INLET  
DETAILS**

SCALE  
**N:1S**

SHEET 1 OF 1 SHEETS

Drawing No.  
**618/336**

**LEGEND**

**[A1 +4.1]** SETTINGS OF POINTS & DEPTH  
(+ ABOVE / - BELOW G.L.)

**NOTE:**  
ALL WORK IS TO BE DONE  
TO SABS 1200

**TEST HOLE**



TH1

LIFE BOUY

UNDERDRAIN (DETAIL V)

PENSTOCK PIPE

SOLUTION TRENCH

HEADWALL

**ISSUED FOR DISCUSSION PURPOSES ONLY**

No.	Amendments	Appr.	Date
C	DRAWING UPDATED		16/07/21
B	DRAWING UPDATED		22/11/20
A	DRAWING UPDATED		08/09/20
0	DRAWING CREATED		16/07/21

Reviewed	Sketch No.
Plotted	Checked
Drawn	Checked
Deleted	Checked

**ECSA 750 693**

For **ALAN ROBINSON** P.Eng



12 Oudewater P.O. Box 2861 Tel: (011) 479-4266  
276 Waterlooven rd NORTRICHTER Hill, 008-10-12-89  
Johannesburg Fax: 086 884 657

Client:

**LIDWALA**

**ESKOM ASH  
HENDRINA**

Description:







**AWRD WEST  
SAFETY DETAILS**

SCALE  
as shown

SHEET OF SHEETS

Drawing No.  
**618/342**

W:\3\2021\618\342\618342.dwg



NOTE:  
ALL WORK IS TO BE DONE  
TO SABS 1200

ISSUED FOR  
DISCUSSION PURPOSES  
ONLY

No.	Author/Reviser	Assg.	Date
B	DRAWING UPDATED		16/02/15
A	DRAWING UPDATED		17/11/14
0	DRAWING CREATED		16/07/13

Author	Alan Robinson
Drawn	
Checked	
Scale	
Sheet	
Project	

ECSA 750 693  
ALAN ROBINSON

12 Overview  
276 Politekniekwaliteit rd  
Normanville  
Johannesburg  
2116  
Tel: (011) 498-4888  
Cell: 0828-10-12-23  
Fax: 086 084 6071


LIDWALA

ESKOM ASH  
HENDRINA

AWRD WEST  
(CLEAR WATER)  
WALL SECTION


SCALE  
N:1S  
SHEET 171 OF 175

Drawings No.  
618/343




Distance	0.0	1629.5	174.0	182.3	1629.5	258.9	268.4	275.0	280.2	1626.5
W.L.		1629.5	174.0	182.3	1629.5	258.9	268.4	275.0	280.2	1626.5
Distance		1629.5	174.0	182.3	1629.5	258.9	268.4	275.0	280.2	1626.5
NGL		1629.5	174.0	182.3	1629.5	258.9	268.4	275.0	280.2	1626.5
Distance		1629.5	174.0	182.3	1629.5	258.9	268.4	275.0	280.2	1626.5
AWR		1629.5	174.0	182.3	1629.5	258.9	268.4	275.0	280.2	1626.5

SECTION B-B



SECTION - AWRD WALL (ASH WATER)



NOTE:  
70kg SAND FILLED  
BALLAST BAGS  
PLACED ON 5m  
GRID ON FLOOR

SECTION - AWRD WALL (CLEAR WATER)



ISSUED FOR DISCUSSION PURPOSES

A	DRAWING UPDATED	22/11/14	
0	DRAWING CREATED	10/07/13	
No.	Amendments	Appr.	Descr.

Drawn	Checked
Design	Drawn
Checked	Design
Drawn	Checked


ECSA 750 693  
 ALAN ROBINSON P. Eng

**ALAN ROBINSON ENGINEERING**  
 CONSULTING ENGINEERS  
 12 Oostervue P.O. Box 2861 Tel: (011) 476-4966  
 27a Waterloovlei rd. NORTRICLIFF Call: 0888-10-12-33  
 Johannesburg Fax: 086 884 8577


Client: **LIDWALA**  
 Project: **ESKOM ASH HENDRINA**

Description: **AWRD WEST INLET DETAILS**



Scale: **N:1S**  
 Sheet of: **3**  
 Drawing No: **618/346**



**FRONT VIEW**



**FRONT VIEW**



NOTE:  
ALL WORK IS TO BE DONE  
TO SABS 1200

ISSUED FOR  
DISCUSSION PURPOSES  
ONLY

No.	Amendments	Rev.	Date
0	DRAWING CREATED		16/07/23

ECSA 750 693

ALAN ROBINSON P.Eng

**ALAN ROBINSON ENGINEERING**  
 CONSULTANTS  
 P.O. Box 2861 Tel: (011) 479-4266  
 27a Weltevreden rd. Call: 082-10-12-23  
 Johannesburg Fax: 086 884 6877


LIDWALA

ESKOM ASH  
HENDRINA


SILT TRAP  
WALL SECTION

SCALE  
as shown

SHEET OF BIE'S  
Drawing No.  
618/350



SECTION B-B



SECTION - SILT TRAP

\* NOTE:  
AT THE END OPPOSITE THE RAMP  
INTO THE SILT TRAP THE BLOCKS  
ARE TO BE PLACED TO THE WALL  
HEIGHT

BARRIER LAYER  
TO DETAIL Q6  
DWG 618 / 400

ISSUED FOR  
DISCUSSION PURPOSES

No.	DATE	BY	REVISION
0			ISSUED FOR DISCUSSION PURPOSES

ECSA 750 693  
For ALAN ROBINSON P.Eng






**WATERPROOFING**  
SPECIALISTS  
P.O. Box 2861 Tel: (011) 479-4266  
276 Weltevreden rd. NORTRICHTER Call: 0858-10-12-29  
Johannesburg Fax: 085 884 8577

Client: **LIDWALA**


Project: **ESKOM ASH HENDRINA**

Description: **HDPE LINER DETAILS**

1. REFER TO THE QUALITY CONTROL CONSTRUCTION MANUAL FOR SPECIFIC DESTRUCTIVE AND NON-DESTRUCTIVE TEST METHODS.
2. ALL SHEETS NEEDED TO BE BEVELED.





**GENERAL LINER DETAILS**  
DETAIL 1



**ANCHOR TRENCH DETAIL**  
DETAIL 2

1. EMBANKMENT AND FLOOR COMPACTED TO 93% MOD AASHTO




**TYPICAL DOUBLE FUSION HOT WEDGE WELD DETAIL**  
DETAIL 3

1. ALL CONCRETE SURFACES TO BE STEEL TROWEL FINISHED WITH CHAMFERED EDGES.


SEE EARTHWORKS SPECIFICATION IN DOCUMENT.

**TYPICAL PIPE BOOT**  
DETAIL 6







**TYPICAL SECTION W-W**



**TYPICAL SECTION Y-Y**



**PLAN - OF OPEN CHANNEL**



**PIPE CROSSING - DETAIL B1**

ISSUED FOR DISCUSSION PURPOSES ONLY

No.	DESCRIPTION	DATE
0	DRAWING CREATED	00/01/13
	Amendments	

No.	DESCRIPTION	DATE
	Checked	
	Drawn	
	Designed	

**ECSA 750 693**  
 For **ALAN ROBINSON** P.Eng

**MANAGEMENT**  
 CONSULTING ENGINEERS  
 P.O. Box 2861 Tel: (011) 478-4266  
 274 Waterlooville rd Call: 0828-10-12-23  
 Johannesburg Fax: 086 884 657

Client: **LIDWALA**

Project: **ESKOM ASH HENDRINA**

Description: **ENERGY DISSIPATION STRUCTURE & PIPE CROSSING**

SCALE: **N:1S**  
 SHEET OF SHEETS

Drawing No. **618/386**

**DETAIL - Z OPEN CHANNEL OUTLET**

ISSUED FOR  
DISCUSSION PURPOSES  
ONLY

No.	Amendments	Appr.	Date
0	DRAWING CREATED		08/07/13

**ECSA 750 693**  
for **ALAN ROBINSON** P.Eng


**WATERMETER**  
WATERMETER ENGINEERING  
P.O. Box 2861 Tel: (011) 479-4266  
276 Weltevreden rd Call: 0858-10-12-89  
Johannesburg Fax: 086 864 8577

Client: **LIDWALA**


Project: **ESKOM ASH  
HENDRINA**

Description: **WADF STANDARD  
DETAILS  
SHEET 1**


SCALE: **N:1S**  
SHEET 1 OF 3 SHEETS  
Drawing No. **618/390**



**FIG 2.2 - DUMP DRAINAGE**



**FIG 3.1 - SECTION THROUGH ASH DAM INDICATING CONSTRUCTION OF THE FIRST ASH BERMS**



**FIG 3.2 - CONSTRUCTION OF THE FIRST BERM & STEP**

ISSUED FOR  
DISCUSSION PURPOSES  
ONLY

DRAWING CREATED		SUBTITLE	
No.	Amendments	Appr.	Date

BOOKS	
Project	Drawings

ECSA 750 693

ALAN ROBINSON

12 October 2010  
11 March 2011  
21 Feb 2015



P.O. Box 2861  
Middelburg Rd  
Blackheath  
Johannesburg  
2115  
Tel: 086 884 867  
Fax: 086 884 867

Client:

LIDWALA

Project:  
**ESKOM ASH  
HENDRINA**


Detail/Id:

**WADF STANDARD  
DETAILS  
SHEET 2**


SCALE  
**N:1S**  
SHEET OF SHEETS

Drawing No.  
**618/391**


1:1 - 2010/01/01



**FIG 3.3 - METHOD OF WALL BUILDING**



**FIG 3.4 - CROSS BERMS ON DAYWALL**



**FIG 3.7 - SECTION AA**

ISSUED FOR  
DISCUSSION PURPOSES  
ONLY

No.	Amendment	Appr.	Date
0	DRAWING CREATED		08/07/13

Drawn	Checked	Reviewed	Approved

ECSA 750 693

ALAN ROBINSON P.Eng



MUZIKWENA  
ENGINEERING & CONSTRUCTION  
ESTABLISHED 1988  
P.O. Box 2861 Tel: (011) 479-6266  
27a Weltevreden rd. NORTRICLIFF Call: 088-10-12-89  
Johannesburg Fax: 088 884 887

LIDWALA


ESKOM ASH  
HENDRINA

WADF STANDARD  
DETAILS  
SHEET 3


SCALE  
N:1S

SHEET 1 OF 3 SHEETS

Drawing No.  
**618/392**




**FIG 3.8 - SECTION**




**FIG 3.15 - PROPOSED PIEZOMETER POSITIONS**





**DETAIL Q6 (AWRD)**  
**( CLASS C BARRIER )**



**DETAIL Q5 (WET ASH)**  
**( CLASS C BARRIER )**

ISSUED FOR DISCUSSION PURPOSES ONLY

No.	Amendments	Appr.	Date
C	DETAILS UPDATED		16/07/15
B	DETAILS UPDATED		15/07/14
A	DETAILS UPDATED		16/09/14
0	DRAWING CREATED		07/12/11

Checked	Drawn	Designed

ECSA 750 693

For ALAN ROBINSON P.Eng

12 Owenview  
27a Weltevreden rd  
Worcester  
Johnannesburg

Tel: (011) 479-4266  
Cell: 082-10-12-23  
Fax: 086 884 657

Client: LIDWALA

Project: ESKOM ASH HENDRINA

Description: WADF & AWRD BARRIER DETAILS

**APPENDIX B  
WATER BALANCE**

**Report by ILANDA Water Services**

**iLanda Water Services CC**  
Reg. No.: CK2011/077571/23

PO Box 44961  
Linden  
2104  
Johannesburg, South Africa

Tel +27 (0)83 408 3241  
Fax +27 (0)86 552 0407  
bruce@ilandawater.co.za  
<http://www.ilandawater.co.za>



## **REPORT ON**

# **HENDRINA ASH DAM WATER BALANCE**

Report No : 0096-Rep-001 Rev 4

Submitted to:

Alan Robinson Consulting Civil & Geotechnical  
Engineers  
12 Crest View  
278 Weltevreden Road  
Johannesburg

### **DISTRIBUTION:**

Alan Robinson Consulting Civil & Geotechnical Engineers  
iLanda Water Services – Library

February 2015

0096

## TABLE OF CONTENTS

<b>SECTION</b>	<b>PAGE</b>
1 INTRODUCTION .....	1
2 STUDY OBJECTIVES .....	1
3 CLIMATE DATA SUMMARY .....	1
3.1 Storm Events .....	1
4 WATER BALANCE METHODOLOGY .....	2
5 WATER BALANCE RESULTS .....	3
5.1 Make-up and Return .....	3
5.2 Decant System and Pool Control .....	4
5.3 Ash Water Return Dam Sizing and Management.....	4
5.4 Return Water System .....	6
6 REFERENCES .....	6

### LIST OF FIGURES

Figure 1: Monthly Average Return and Make-up Flows	4
Figure 2: Location of ash water return dams	5

### LIST OF TABLES

Table 1: Climate data summary .....	1
Table 2: Peak 24-hr rainfall depths.....	1

### LIST OF APPENDICES

Appendix A	Water Balance Diagram
Appendix B	Input information

### REVISION TRACKING

- Rev 0: Original document
- Rev 1: Review comments addressed
- Rev 2: Water balance diagram updated
- Rev 3: West AWRD capacity updated
- Rev 4: Minor text changes

## 1 INTRODUCTION

Alan Robinson Consulting Civil & Geotechnical Engineers commissioned iLanda Water Services CC to calculate the water balance for the proposed Hendrina Ash Dam. This report details methods of analysis, the water balance results and the hydrology relating to the ash dam for a pre-feasibility study.

## 2 STUDY OBJECTIVES

The study objectives are as follows:

- Size the ash water return dam
- Size the decant system
- Size the return water pumping system

## 3 CLIMATE DATA SUMMARY

Monthly rainfall data for the area was obtained from the CCWR (Computing Centre for Water Research, Natal University) database. Gauge number 0516480 (Schoonoord) was used. Evaporation data and its monthly distribution were sourced from the Water Resources of South Africa Study data set, zone 4A (Midgley et al., 1990). Runoff factors were informed by average runoff for the quaternary catchment B12B, documented in the Water Resources of South Africa Study report (Middleton et al., 2009).

The mean annual precipitation and mean annual evaporation data are presented in Table 1.

*Table 1: Climate data summary*

Parameter	Value (mm)
Mean annual rainfall	648
Mean annual evaporation (S-Pan)	1 552

### 3.1 Storm Events

Peak rainfall data was sourced from Adamson's (Adamson, 1981) TR102 gauge 0516480 (Schoonoord). The 50-year and 100-year, 24-hour rainfall depths are presented in Table 2.

*Table 2: Peak 24-hr rainfall depths*

Recurrence Interval	24-hr rainfall depth (mm)
50-year	126
100-year	144

## 4 WATER BALANCE METHODOLOGY

The water balance is a continuous monthly time step water balance. The water balance represents average flows between components and along hydrological interfaces.

A static average water balance diagram is provided in Appendix A. The diagram represents average flows between components and along hydrological interfaces. These are the average flows, as calculated by the continuous monthly water balance. The inflows are presented on the left of the water balance diagram. The components and inter-facility flows are shown in the centre of the water balance diagram. The outflows are shown on the right of this diagram. The direction of water movement is shown in black arrows. The values next to the arrows represent average flows in m<sup>3</sup>/day. Clean water flows are shown in blue, while dirty flows are shown in red.

The continuous monthly water balance contains the following components:

- Ash dam wet beach
- Ash dam dry beach
- Ash dam pool
- Slurry stream (slurry water)
- Decant stream
- Ash return water dam
- Return water stream (return water)

The power station is external to the water balance and is assumed to be a source of slurry water and a receptor of return water. The make-up source is included in the slurry water.

The main inflows (sources) and outflows (sinks) are:

### Inflows (Sources)

- Rainfall falling on the ash dam basin.
- Slurry water.

### Outflows (Sinks)

- Evaporation losses from the ash dam and ash return water dam.
- Seepage to deep groundwater from the ash dam basin and ash return water dam (both these facilities are lined).
- Interstitial lockup in the ash dam.
- Return to plant.

One of the fundamental principles of a water balance is that inflows must equal outflows unless the difference is accommodated in storage changes. The water balance is a steady state water balance and therefore storage changes are assumed to be zero.

Runoff factors for the dry beach were based on experience and documented runoff factors of catchments in similar climates in South Africa - documented in the Water Resources of South Africa, 2005 Study (Middleton and Bailey, 2009). The input data is summarised in Appendix B.

## **5 WATER BALANCE RESULTS**

### **5.1 Make-up and Return**

The water balance is a deficit water balance, and significant quantities of make-up water will be required. The make-up requirements are seasonal. During the wet season, storm water will be harvested from the ash dam basin and the external catchment above the ash dam. Returns consequently increase and make-up requirements decrease. The opposite is true during the dry season.

The average annual return is 79% of the slurry water. The low density slurry results in interstitial and evaporative losses forming a small percentage of the total water in the system.

Make-up demands range between 2 650 m<sup>3</sup>/day and 6 700 m<sup>3</sup>/day. The monthly water balance results were statistically analysed to produce monthly average return and make-up flows. These are presented in Figure 1.




Figure 1: Monthly Average Return and Make-up Flows

## 5.2 Decant System and Pool Control

The penstock is sized to remove the runoff generated by a 50-year, 24-hour design storm in 3 days. This is to minimise the time that a large pool is stored on the ash dam basin. The storm water volume generated during a 50-year, 24-hour storm event is approximately 123 500 m<sup>3</sup>. The ash dam requires a penstock capable of decanting 41 170 m<sup>3</sup>/day, or 1 715 m<sup>3</sup>/hr, assuming a 24-hour decanting day. Two 750 mm diameter penstocks or three 510 mm diameter penstocks will have sufficient capacity to decant this volume with a depth of no more than 160 mm above the penstock crest. The outlet pipe should have a capacity larger than the required decant rate.

This will ensure that the pool volume rarely exceeds 50 000 m<sup>3</sup> provided the penstock is operated to the design intent. Water should not be stored on the ash dam basin. This will have the benefit of reducing water losses, decreasing make-up volumes, increased consolidation rates of the ash and increasing the stability of the ash dam.

## 5.3 Ash Water Return Dam Sizing and Management

The ash water return dam must comply with Government Notice 704 of the South African National Water Act, Act 36 of 1998. The dam sizing methodology was therefore based on the excess water resulting from a long term monthly water balance, plus the 50-year storm runoff volume. The 50-year storm was added to the monthly time series because individual storms during the month are not modelled and are averaged out during the month.



In view of the above, it is concluded that the ash water return dam should have a capacity of at least 123 000 m<sup>3</sup>. The ash return water dams may require registration with the Department of Water Affairs' Dam Safety Office. Topography and site specific water management requirements dictate that three dams are required. The three dams are described below:

The main return water dam (West AWRD – North Paddock) should have a capacity of at least 31 600 m<sup>3</sup>. This water should be pumped empty at a rate of at least 7 l/s. The main return water dam (West AWRD – South Paddock) should have a capacity of at least 91 400 m<sup>3</sup>. The penstocks should discharge into this dam via a silt trap.

A 10 000 m<sup>3</sup> dam (East AWRD) is required in the eastern side of the ash dam to collect storm water from the ash dam sides and drainage water from the south western corner of the ash dam. This water should be pumped into the solution trench and run down to the main return water dam (West AWRD) and then returned to the power station, either directly or via the existing AWR dams. The pumps should have a capacity of at least 3.5 l/s. This dam will only be required once the ash dam rises above the topography in the south eastern corner. It therefore does not contribute to the 123 000 m<sup>3</sup> required dam capacity in the early years of the dump life.

The ash return water dams should be operated as empty as possible and not used to store water for future consumption. All captured storm water should be consumed as fast as possible. If operated correctly, the dams should be mostly dry and should only contain water for short periods after large storms. The locations of the dams are shown in Figure 2.




Figure 2: Location of ash water return dams

#### **5.4 Return Water System**

The water return system should be sized to return at least 100% of the slurry water requirement. This is 805 044 m<sup>3</sup>/month, or 26 500 m<sup>3</sup>/day. This equates to 1 200 m<sup>3</sup>/hr for a 22-hour pumping day.

### **6 REFERENCES**

Middleton, B.J. and Bailey, A.K.. *Water Resources of South Africa, 2005 study (WR2005)*, 2009. WRC Report No TT 382/08.



### **ILANDA WATER SERVICES**

BN Randell

C:\ILANDA\PROJECTS\0096 HENDRINA WATER BALANCE\REPORT\REV 4\0096-REP-001 REV 4 HENDRINA ASH DAM WATER BALANCE.DOCX

**APPENDIX A**

**WATER BALANCE DIAGRAM**




**APPENDIX B**

**INPUT INFORMATION**

Parameter	Value	Units	Source
Deposition rate	210,784	tpm	Alan Robinson
SG	2.36		Alan Robinson
Slurry density	20.8%	solids by mass	Alan Robinson
Ash placed density	55.0%	solids by mass	Estimate based on experience of similar projects
Ash consolidated density	62.0%	solids by mass	Estimate based on experience of similar projects
Ash consolidated dry density	0.96	tonne/m <sup>3</sup>	Estimate based on experience of similar projects
Interstitial storage	16%	of slurry water	Estimate based on experience of similar projects
Ash dam basin area	1,234,297	m <sup>2</sup>	Alan Robinson
Max pool area	80,000	m <sup>2</sup>	Estimate based on experience of similar projects
Pool seepage rate	2.00E-07	m/s	Estimate based on experience of similar projects
Wet beach size	25%	of total beach area	Estimate based on experience of similar projects
Wet beach runoff factor	80%		Estimate based on experience of similar projects
Ash dam upstream catchment	0	m <sup>2</sup>	Alan Robinson

### Catchment and dry beach rainfall/runoff response



**APPENDIX C**  
**BUDGET COSTING**

**HENDRINA AWRD's - REV C**

## 1 - SITE ESTABLISHMENT

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
1.1		1 - SITE ESTABLISHMENT					
1.1.1		Site Establishment (fixed)	LS	1.0	0.00	0	00
1.1.2		Site Establishment (time)	mths	12.0	0.00	0	00
1.1.3		Preliminary and General (fixed)	LS	1.0	5344225.00	5344225	00
1.1.4		Preliminary and General (time)	mths	12.0	0.00	0	00
Total Carried Forward To Summary						5344225	00
2.1		2 - SITE CLEARING					
		Clearing and grubbing					
2.1.1		(a) Drainage channels & drains	ha	1.0	10000.00	10000	00
		Clearing and grubbing within "footprint" including bush and trees.					
2.1.2		(a) AWRD (East)	ha	1.3	15000.00	19500	00
2.1.3		(b) AWRD (West)	ha	6.0	15000.00	90000	00
2.1.4		c) Silt Trap	ha	0.1	15000.00	1500	00
2.1.5		Load to clear, haul and dump existing stockpiles on site as directed. (Provisional)	m <sup>3</sup>	0.0	0.00	0	00
Total Carried Forward To Summary						121000	00
3.1		3 - EXCAVATIONS					
		Note: No "double" handling from stockpiles will be paid for, unless indicated.					
		Excavations for clean Stormwater diversion trench and berm construction to Detail.					
3.1.1		(a) AWRD	m <sup>3</sup>	100.0	30.00	3000	00
		Remove topsoil within dam footprint to nominal depth of 200mm and stockpile on site within 1,0km					
3.1.2		(a) AWRD (East)	m <sup>3</sup>	2600.0	20.00	52000	00
3.1.3		(b) AWRD (West)	m <sup>3</sup>	12000.0	20.00	240000	00
3.1.4		(c) Silt Trap	m <sup>3</sup>	200.0	20.00	4000	00
		Excavate to stockpile from basin					
3.1.5		a) AWRD (East)	m <sup>3</sup>	17300.0	25.00	432500	00
Total Carried Forward						731500	00



ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
Brought Forward						731500	00
3.1.6		b) AWRD ( West)	m <sup>3</sup>	151000.0	25.00	3775000	00
3.1.7		c) SiltTrap	m <sup>3</sup>	1000.0	25.00	25000	00
		Excavate selected material to stockpile for clay liner for AWRD (East)					
3.1.8		(a) To layer b (2 x150mm)	m <sup>3</sup>	0.0	25.00	0	00
3.1.9		(b) To layer d (1x 200mm)	m <sup>3</sup>	0.0	25.00	0	00
		Excavate selected material to stockpile for clay liner for AWRD (West)					
3.1.10		(a) To layer b (2x150)	m <sup>3</sup>	15000.0	25.00	375000	00
3.1.11		(b) To layer d (1x200mm)	m <sup>3</sup>	0.0	25.00	0	00
		Excavate selected material to stockpile for clay liner for SILT TRAP					
3.1.12		(a) To layer b (2x150mm)	m <sup>3</sup>	600.0	25.00	15000	00
3.1.13		(b) To layer d (1x200mm)	m <sup>3</sup>	0.0	25.00	0	00
		Excavate selected material from stockpile for Base preparation Layer g					
3.1.14		(a) AWRD (East)	m <sup>3</sup>	0.0	30.00	0	00
3.1.15		(b) AWRD (West)	m <sup>3</sup>	0.0	30.00	0	00
3.1.16		c) Silt Trap	m <sup>3</sup>	0.0	30.00	0	00
3.2		POOR SUBGRADE					
3.2.1		Excavate unsuitable soft and wet material to spoil	m <sup>3</sup>	1500.0	35.00	52500	00
3.2.2		Supply and place A6 Geotextile to floor of excavation if required as directed (provisional)	m <sup>2</sup>	5000.0	15.00	75000	00
3.2.3		Supply and place nominal 200mm Dump rock and "blind" with finer material as directed to levels given, from stockpile on mine	m <sup>3</sup>	500.0	100.00	50000	00
3.3		DEWATERING					
Total Carried Forward						5099000	00

**HENDRINA AWRD's - REV C**

## 3 - EXCAVATIONS

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
Brought Forward						5099000	00
3.3.1		To supply, operate and maintain dewatering and pumping equipment as directed.	days	40.0	2000.00	80000	00
Total Carried Forward To Summary						5179000	00
4.1		4 - EARTHWORKS  Note: No "double" handling from stockpiles will be paid for, unless indicated.  Load from stockpiles to construct and compact to 95% PROCTOR in 150mm layers including levelling trimming and forming side slopes					
4.1.1		(a) AWRD (East)	m <sup>3</sup>	11100.0	40.00	444000	00
4.1.2		(b) AWRD (West)	m <sup>3</sup>	8730.0	40.00	349200	00
4.1.3		c) Silt Trap	m <sup>3</sup>	500.0	40.00	20000	00
4.1.4		Excavate to spoil within 1,0km freehaul	m <sup>3</sup>	150000.0	25.00	3750000	00
4.1.5		Excavate from borrow on site, load, haul & place 200mm G5 Quality material & compact to 95% PROCTOR to floor of silt trap (max particle size 10mm)	m <sup>3</sup>	200.0	50.00	10000	00
		Load from Stockpile place and compact to 95% PROCTOR to lines and levels to form clay liner AWRD (East)					
4.1.6		(a) To layer b (2x150mm)	m <sup>3</sup>	2800.0	50.00	140000	00
4.1.7		(b) To layer d (1x200mm)	m <sup>3</sup>	0.0	50.00	0	00
		Load from Stockpile place and compact to 95% PROCTOR to lines and levels to form clay liner AWRD (West)					
4.1.8		(a) To layer b (2x150mm)	m <sup>3</sup>	15000.0	50.00	750000	00
4.1.9		(b) To layer d (1x200mm)	m <sup>3</sup>	0.0	50.00	0	00
		Load from Stockpile place and compact to 95% PROCTOR to lines and levels to form clay liner SILT TRAP					
4.1.10		(a) To layer b (2x150mm)	m <sup>3</sup>	600.0	50.00	30000	00
4.1.11		(b) To layer d (1x200mm)	m <sup>3</sup>	0.0	50.00	0	00
		Place topsoil to sideslopes of of wall 200mm layer					
Total Carried Forward						5493200	00

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
Brought Forward						5493200	00
4.1.12		(a) AWRD (East)	m <sup>3</sup>	100.0	40.00	4000	00
4.1.13		(b) AWRD (West)	m <sup>3</sup>	800.0	40.00	32000	00
4.1.14		c) Silt Trap	m <sup>3</sup>	50.0	40.00	2000	00
		Supply and place 25mm Slag to crest of wall in 200mm layer					
4.1.15		(a) AWRD (East)	m <sup>3</sup>	304.0	250.00	76000	00
4.1.16		(b) AWRD (West)	m <sup>3</sup>	942.0	250.00	235500	00
4.1.17		c) Silt Trap	m <sup>3</sup>	200.0	250.00	50000	00
4.2		FLOOR PREPARATION					
		Rip and compact 200mm insitu floor 93% Mod AASHTO					
4.2.1		(a) AWRD (East)	m <sup>3</sup>	4400.0	20.00	88000	00
4.2.2		(b) AWRD (West)	m <sup>3</sup>	25000.0	20.00	500000	00
4.2.3		c) Silt Trap	m <sup>3</sup>	400.0	20.00	8000	00
		Load from stockpile, haul and place 200mm and compact to 90% Mod AASHTO Density to base preparation layer					
4.2.4		(a) AWRD (East)	m <sup>3</sup>	1700.0	50.00	85000	00
4.2.5		(b) AWRD (West)	m <sup>3</sup>	10000.0	50.00	500000	00
4.2.6		c) Silt Trap	m <sup>3</sup>	200.0	50.00	10000	00
Total Carried Forward To Summary						7083700	00
5.1		GEOTEXTILE (KAYTECH)					
		Supply and place geotextile to floor and sides A4 Bidim (Upper)					
5.1.1		(a) AWRD (East)	m <sup>2</sup>	8600.0	10.00	86000	00
5.1.2		(b) AWRD (West)	m <sup>2</sup>	50000.0	10.00	500000	00
5.1.3		(c) To Silt Traps	m <sup>2</sup>	1000.0	10.00	10000	00
		Supply and place geotextile to floor and sides A4 Bidim (Lower)					
5.1.4		(a) AWRD (East)	m <sup>2</sup>	0.0	10.00	0	00
5.1.5		(b) AWRD (West)	m <sup>2</sup>	0.0	10.00	0	00
Total Carried Forward						596000	00

**HENDRINA AWRD's - REV C****5 - BARRIER SYSTEM**

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
Brought Forward						596000	00
5.1.6		(c) To Silt Traps	m <sup>2</sup>	1000.0	10.00	10000	00
5.1.7		Supply all labour and materials to construct 1200 Ø manhole rings to pump sump as detailed. (including cover)	No	1.0	5000.00	5000	00
5.1.8		Supply and place KAYTECH Flownet 700HP (a) AWRD (East)	m <sup>2</sup>	8600.0	50.00	430000	00
5.1.9		(b) AWRD (West)	m <sup>2</sup>	50000.0	50.00	2500000	00
5.1.10		(c) To Silt Traps	m <sup>2</sup>	1000.0	50.00	50000	00
Total Carried Forward To Summary						3591000	00
6.1		6 - DAM LINER  To: HDPE SANS 10409:2005 and SANS1526:2003  Excavate anchor trench to wall and backfill after liner has been placed.					
6.1.1		(a) AWRD (East)	m <sup>3</sup>	200.0	200.00	40000	00
6.1.2		(b) AWRD (West)	m <sup>3</sup>	425.0	200.00	85000	00
6.1.3		(c) To Silt Trap	m <sup>3</sup>	85.0	200.00	17000	00
6.1.4		Trim earthworks to supplier tolerances prior to placing liner (a) AWRD (East)	m <sup>2</sup>	8600.0	1.00	8600	00
6.1.5		(b) AWRD (West)	m <sup>2</sup>	35000.0	1.00	35000	00
6.1.6		(c) To Silt Trap	m <sup>2</sup>	2000.0	1.00	2000	00
6.1.7		Supply and lay AQUATAN HDPE liner 2,0mm thick to SABS and supplier standard details. (a) AWRD (East)	m <sup>2</sup>	8600.0	70.00	602000	00
6.1.8		(b) AWRD (West)	m <sup>2</sup>	35000.0	70.00	2450000	00
6.1.9		(c) To Silt Traps	m <sup>2</sup>	2000.0	70.00	140000	00
6.1.10		Supply lay, and anchor ARMORFLEX 140 Blocks with soilcrete infill to supplier's specifications to floor, walls and access road of Silt Trap	m <sup>2</sup>	2000.0	200.00	400000	00
Total Carried Forward						3779600	00

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
Brought Forward						3779600	00
6.1.11		Supply and place Kaytech A10 beneath AMORFLEX	m <sup>2</sup>	2000.00	20.00	40000	00
Total Carried Forward To Summary						3819600	00
7.1		7 - DRAINAGE					
		Excavate to form channel inlet to PCD					
7.1.1		(a) AWRD (East)	m <sup>3</sup>	50.0	50.00	2500	00
7.1.2		(b) AWRD (West)	m <sup>3</sup>	200.0	50.00	10000	00
7.1.3		(c) To Silt Traps	m <sup>3</sup>	30.0	50.00	1500	00
		Construct concrete headwalls complete to detail					
7.1.4		(a) AWRD (East)	No	2.0	2000.00	4000	00
7.1.5		(b) AWRD (West)	No	4.0	2000.00	8000	00
7.1.6		(c) To Silt Traps	No	4.0	200.00	800	00
		Construct concrete pipe collar to supplier details through lining					
7.1.7		(a) AWRD (East)	No	2.0	3000.00	6000	00
7.1.8		(b) AWRD (West)	No	2.0	3000.00	6000	00
7.1.9		(c) To Silt Traps	No	2.0	3000.00	6000	00
		Supply and lay 750mm diam. concrete spigot and socket 100 D pipes on Class B bedding to inlets					
7.1.10		(a) AWRD (East)	m	30.0	1200.00	36000	00
7.1.11		(b) AWRD (West)	m	30.0	1200.00	36000	00
7.1.12		(c) To Silt Traps	m	30.0	1200.00	36000	00
7.1.13		Class B bedding	m <sup>3</sup>	6.0	400.00	2400	00
		Supply and place 2,5mm wire Galvanised Gabions and Reno to stormwater drains.					
7.1.14		Drain 1	m <sup>3</sup>	0.0	0.00	0	00
		To 2,0mm HDPE liner under Gabions					
7.1.15		Drain 1	m <sup>2</sup>	0.0	0.00	0	00
Total Carried Forward						155200	00

**HENDRINA AWRD's - REV C**

## 7- DRAINAGE

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
Brought Forward						155200	00
7.1.16		To A4 Geotextile under Gabions Drain 1	m <sup>2</sup>	0.0	0.00	0	00
7.1.17		SPILLWAY (TO DETAIL) AWRD - East Earthworks	m <sup>3</sup>	50.0	60.00	3000	00
7.1.18		Supply and place 600mm diam Spigot and Socket 100D concrete pipes	m	30.0	1100.00	33000	00
7.1.19		Concrete to head walls to detail SPILLWAY (TO DETAIL) AWRD - West	No	2.0	2200.00	4400	00
7.1.20		Earthworks	m <sup>3</sup>	50.0	60.00	3000	00
7.1.21		Supply and place 600mm diam Spigot and Socket 100D concrete pipes	m	30.0	1100.00	33000	00
7.1.22		Concrete to head walls to detail	No	2.0	2200.00	4400	00
Total Carried Forward To Summary						236000	00
8.1		GENERAL					
8.1.1		30 MPa Concrete Edge Beam to Roadway (a) AWRD (East)	m <sup>3</sup>	1.1	1500.00	1650	00
8.1.2		(b) AWRD (West)	m <sup>3</sup>	1.1	1500.00	1650	00
8.1.3		Reconstruct 5m wide Bakkie Access Road, and compact to perimeter (a) AWRD (East)	m <sup>2</sup>	1900.0	50.00	95000	00
8.1.4		(b) AWRD (West)	m <sup>2</sup>	5900.0	50.00	295000	00
8.1.5		Supply & install crawl-net complete (4No) (a) AWRD (East)	m <sup>2</sup>	200.0	50.00	10000	00
8.1.6		(b) AWRD (West)	m <sup>2</sup>	200.0	50.00	10000	00
8.1.7		(c) To Silt Traps	m <sup>2</sup>	200.0	50.00	10000	00
8.1.8		Supply & install life-buoy & mounting Pole complete (a) AWRD (East)	No	4.0	500.00	2000	00
8.1.9		(b) AWRD (West)	No	8.0	500.00	4000	00
8.1.10		(c) To Silt Traps	No	4.0	500.00	2000	00
Total Carried Forward To Summary						431300	00

## SUMMARY OF SECTIONS

SECTION	DESCRIPTION	AMOUNT (RAND)	
1	SITE ESTABLISHMENT	5344225	00
2	SITE CLEARING	121000	00
3	EXCAVATIONS	5179000	00
4	EARTHWORKS	7083700	00
5	BARRIER SYSTEM	3591000	00
6	DAM LINER	3819600	00
7	DRAINAGE	236000	00
8	GENERAL	431300	00
	SUB TOTAL	25805825	00
		0	00
	5 % CONTINGENCIES	25805825	00
		1290291	25
	VAT @ 14 % :	27096116	25
		0	00
Total Carried Forward To Summary Of Schedules		27096116	25

***HENDRINA ASH DAM E - REV B***

## 1 -SITE ESTABLISHMENT

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
1.1		1 - SITE ESTABLISHMENT					
1.1.1		Site Establishment (fixed)	LS	1.0	68166541.00	68166541	00
1.1.2		Preliminary and General (time)	mths	30.0	0.00	0	00
1.1.3		Preliminary and General (fixed)	LS	0.0	0.00	0	00
1.1.4		Site Establishment (time)	mths	30.0	0.00	0	00
Total Carried Forward To Summary						68166541	00
2.1		2 - SITE CLEARING					
2.1.1		Clearing and grubbing beneath Ash Dam	ha	128.0	10000.00	1280000	00
2.1.2		Clearing to drains	ha	1.0	10000.00	10000	00
Total Carried Forward To Summary						1290000	00
3.1		3 - EXCAVATIONS					
3.1.1		Remove topsoil to nominal depth of 250mm and stockpile on site within 0,5km below Ash Dam	m <sup>3</sup>	320000.0	20.00	6400000	00
		Remove material to levels given					
3.1.2		a) Cut to fill below Ash Dam	m <sup>3</sup>	249000.0	30.00	7470000	00
3.1.3		b) Cut unsuitable to spoil or stockpile on site	m <sup>3</sup>	700000.0	20.00	14000000	00
3.1.4		c) Cut to Stockpile 500mm subsoil within 1,0km	m <sup>3</sup>	640000.0	25.00	16000000	00
		Excavations for clean Stormwater diversion trenches and berm construction					
3.1.5		(a) Soft Material	m <sup>3</sup>	2000.0	30.00	60000	00
3.1.6		(b) Extra over for hard material	m <sup>3</sup>	500.0	250.00	125000	00
3.1.7		(c) Extra over to form berm	m <sup>3</sup>	1000.0	15.00	15000	00
		Excavations to stockpile for drains to Detail in soft material					
3.1.8		(a) Solution Trench	m <sup>3</sup>	7700.0	30.00	231000	00
3.1.9		(b) Penstock pipe	m <sup>3</sup>	5320.0	30.00	159600	00
3.1.10		(c) Toe Drain	m <sup>3</sup>	10700.0	50.00	535000	00
3.1.11		(d) Main under drain	m <sup>3</sup>	17900.0	50.00	895000	00
Total Carried Forward						45890600	00



**HENDRINA ASH DAM E - REV B**

## 3 - EXCAVATIONS

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
Brought Forward						45890600	00
3.1.12		(g) Extra over for hard material for drains	m <sup>3</sup>	2000.0	250.00	500000	00
3.1.13		(h) e.o for excavation in Wet Conditions Excavate selected material to stockpile	m <sup>3</sup>	5000.0	15.00	75000	00
3.1.14		(a) To clay layer b (2x150mm)	m <sup>3</sup>	0.0	25.00	0	00
3.1.15		(b) To clay layer d (1x200mm)	m <sup>3</sup>	0.0	25.00	0	00
3.1.16		(c) For starter wall	m <sup>3</sup>	960000.0	25.00	24000000	00
3.2		POOR SUBGRADE					
3.2.1		Excavate unsuitable soft and wet material to spoil	m <sup>3</sup>	50000.0	35.00	1750000	00
3.2.2		Supply and place A6 Geotextile to floor of excavation if required as directed (provisional)	m <sup>2</sup>	5000.0	15.00	75000	00
3.2.3		Supply and place nominal 200mm Dump rock and "blind" with finer material as directed to levels given, from stockpile on mine	m <sup>3</sup>	5000.0	100.00	500000	00
Total Carried Forward To Summary						72790600	00
4.1		EARTHWORKS					
4.1.1		Doze "push up" starter walls including levelling trimming and to Ash Dam perimeter.	m <sup>3</sup>	0.0	25.00	0	00
4.1.2		Excavate selected material to stockpile for Base preparation Layer g (1 x 200mm)	m <sup>3</sup>	0.0	25.00	0	00
4.1.3		Rip in situ material to a depth of 200mm and compact to 93% Mod AASHTO Density, under Ash Dam Load from stockpiles to construct and compact to 95% PROCTOR in 150mm layers including levelling trimming and forming side slopes and including freehaul up to 1,0km	m <sup>3</sup>	256000.0	15.00	3840000	00
4.1.4		(a) Starter Wall	m <sup>3</sup>	960000.0	30.00	28800000	00
4.1.5		(b) Clay layer b (2 x 150mm)	m <sup>3</sup>	384000.0	30.00	11520000	00
4.1.6		(c) Clay layer d (1 x 200mm)	m <sup>3</sup>	0.0	30.00	0	00
Total Carried Forward						44160000	00

**HENDRINA ASH DAM E - REV B**

## 4 - EARTHWORKS

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
Brought Forward						44160000	00
4.1.7		(d) Base prep layer (1 x 200mm)	m <sup>3</sup>	0.0	30.00	0	00
Total Carried Forward To Summary						44160000	00
5.1		<b>5 - BARRIER SYSTEM</b> Supply and place 19mm stone to drains & pipe surround to Detail Ash Dam					
5.1.1		a) Finger Drain Leachate layer a	m <sup>3</sup>	19200.0	300.00	5760000	00
5.1.2		b) Main Drain	m <sup>3</sup>	17900.0	300.00	5370000	00
5.1.3		c) Toe Drain	m <sup>3</sup>	10700.0	300.00	3210000	00
5.1.4		d) leakage detection underdrain layer e	m <sup>3</sup>	19200.00	300.00	5760000	00
5.1.5		Supply and place A4 Bidim (Lower) geotextile to floor	m <sup>2</sup>	1280000.0	10.00	12800000	00
5.1.6		Supply and place A4 Bidim (Separation) geotextile to floor	m <sup>2</sup>	128000.00	10.00	1280000	00
5.1.7		Supply and place A4 Bidim (Upper) geotextile to floor	m <sup>2</sup>	128000.0	10.00	1280000	00
5.1.8		Supply and place A4 Bidim (Separation) geotextile to the floor	m <sup>2</sup>	0.00	10.00	0	00
5.1.9		Load haul and place washed river sand to Main and Toe drain	m <sup>3</sup>	9000.0	300.00	2700000	00
5.1.10		Supply all labour and materials to construct manholes as detailed.	No	2.0	4500.00	9000	00
5.1.11		Supply and place Class 16 UPVC pipes with elbow into Solution Trench	m	4500.0	50.00	225000	00
Total Carried Forward To Summary						38394000	00
6.1		<b>6 - LINER SYSTEM</b> To: HDPE SANS 10409:2005 and SANS1526:2003 Excavate anchor trench and backfill after liner has been placed.					
6.1.1		(a) Ash Dam E	m <sup>3</sup>	2000.0	200.00	400000	00
6.1.2		Trim earthworks to supplier tolerances prior to placing liner (a) Ash Dam E	m <sup>2</sup>	1280000.0	1.00	1280000	00
Total Carried Forward						1680000	00

**HENDRINA ASH DAM E - REV B****6 - LINER SYSTEM**

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
Brought Forward						1680000	00
6.1.3		Supply and lay embossed AQUATAN HDPE liner 1,5mm thick to SABS and supplier standard details to ADF.	m <sup>2</sup>	1190000.0	50.00	59500000	00
Total Carried Forward To Summary						61180000	00
7.1		<b>7 - PENSTOCK AND DECANT SYSTEM</b>					
7.1.1		Supply and install 750mm dia 100D Spigot and Socket with insitu surround	m	790.0	3500.00	2765000	00
7.1.2		Supply and install Class B granular pipe bedding	m <sup>3</sup>	700.0	250.00	175000	00
7.1.3		Supply all material and labour to construct penstock intake including shuttering, fittings, reinforcing, concrete	No	3.0	12000.00	36000	00
7.1.4		Supply and place penstock rings (750mm diam) with insitu surround	No	100.0	520.00	52000	00
7.1.5		Supply and install catwalks allowing for surround to penstock intakes excavations concrete timber and all fittings	m	100.0	2200.00	220000	00
7.1.6		Timber platforms to penstock outlets	No	3.0	6000.00	18000	00
Total Carried Forward To Summary						3266000	00
8.1		<b>8 - FENCING</b>					
8.1.1		Clear 3,0m wide strip	ha	0.6	10000.00	6000	00
8.1.2		Supply and erect fencing including concrete and all fittings - 5 strand fence	m	2000.0	28.00	56000	00
8.1.3		Supply and erect farm gates	No	4.0	3800.00	15200	00
8.1.4		Supply and erect warning signs on fencing	No	15.0	180.00	2700	00
8.1.5		Dismantle existing fences	m	2000.0	10.00	20000	00
Total Carried Forward To Summary						99900	00
9.1		<b>9 - STORM WATER/DRAINAGE</b>					
		To trim and compact floor and sides to 93% Mod AASHTO to solution Trench					
9.1.1		a) Northern Drain	m <sup>2</sup>	6550.0	2.50	16375	00
Total Carried Forward						16375	00

**HENDRINA ASH DAM E - REV B**

## 9 - STORM WATER/DRAINAGE

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R	c
Brought Forward						16375	00
9.1.2		b) Southern Drain	m <sup>2</sup>	6000.0	2.50	15000	00
9.1.3		c) Eastern Drain	m <sup>2</sup>	3200.0	2.50	8000	00
		To supply, place and finish 125mm 25 MPa concrete to Solution Trenches					
9.1.4		a) Northern Drain	m <sup>3</sup>	820.0	2500.00	2050000	00
9.1.5		b) Southern Drain	m <sup>3</sup>	750.0	2500.00	1875000	00
9.1.6		c) Eastern Drain	m <sup>3</sup>	400.0	2500.00	1000000	00
		To supply and place 395 mesh to concrete in solution trenches					
9.1.7		a) Northern Drain	t	26.0	13000.00	338000	00
9.1.8		b) Southern Drain	t	24.0	13000.00	312000	00
9.1.9		c) Eastern Drain	t	13.0	13000.00	169000	00
9.1.10		Wingwalls / Head walls to pipe crossing	No	2.0	9000.00	18000	00
		Supply and place rockfill to fill SABS Gabions to open drains stepped to detail.					
9.1.11		(a) To steps	m <sup>3</sup>	50.0	1200.00	60000	00
9.1.12		(b) To Detail J	m <sup>3</sup>	30.0	1200.00	36000	00
9.1.13		Supply and place A6 Geotextile below Gabions	m <sup>2</sup>	58.0	15.00	870	00
9.1.14		Supply and place 2,00mm HDPE liner below Gabions	m <sup>2</sup>	58.0	70.00	4060	00
9.1.15		Supply & install 20 MPa concrete filled 75mm Geocells to spillway	m <sup>2</sup>	50.0	200.00	10000	00
Total Carried Forward To Summary						5912305	00
		10 - ACCESS ROAD					
10.1		SITE CLEARING					
10.1.1		Clearing and grubbing for access road	ha	1.2	10000.00	12000	00
10.1.2		Remove unsuitable material (topsoil to nominal depth of 150mm) and spoil on site	m <sup>3</sup>	1800.0	20.00	36000	00
		Earthworks					
Total Carried Forward						48000	00




***HENDRINA ASH DAM E - REV B***

## SUMMARY OF SECTIONS


SECTION	DESCRIPTION	AMOUNT (RAND)	
1	SITE ESTABLISHMENT	68166541	00
2	SITE CLEARING	1290000	00
3	EXCAVATIONS	72790600	00
4	4 - EARTHWORKS	44160000	00
5	BARRIER SYSTEM	38394000	00
6	LINER SYSTEM	61180000	00
7	PENSTOCK AND DECANT SYSTEM	3266000	00
8	FENCING	99900	00
9	STORM WATER/DRAINAGE	5912305	00
10	ACCESS ROAD	129000	00
	SUB TOTAL	295388346	00
		0	00
	CONTINGENCIES 5 % :	295388346	00
		14769417	30
	VAT @ 14 % :	310157763	30
		43422086	86
Total Carried Forward To Summary Of Schedules		353579850	16

**APPENDIX D**  
**STABILITY AND RATE OF RISE**




	Project			SLIDE - An Interactive Slope Stability Program	
	Analysis Description				
	Drawn By	Scale	1:2634		Company
	Date	2013/07/18, 12:49:13 PM		File Name	







	Project			SLIDE - An Interactive Slope Stability Program		
	Analysis Description					
	Drawn By			Scale 1:2902		Company
	Date 2013/07/18, 12:49:13 PM			File Name Section 1.slim		



	Project			SLIDE - An Interactive Slope Stability Program		
	Analysis Description					
	Drawn By		Scale		Company	
	Date		2013/07/18, 12:49:13 PM		File Name	
				Section 2 MOD.slim		





	Project		
	SLIDE - An Interactive Slope Stability Program		
	Analysis Description		
	Drawn By	Scale 1:2591	Company
Date	2013/07/18, 12:49:13 PM	File Name	Section 2 MOD WEDGE.slim




SLIDEINTERPRET 6.023


Project			SLIDE - An Interactive Slope Stability Program		
Analysis Description					
Drawn By		Scale 1:2016		Company	
Date		2013/07/19, 10:38:07 AM		File Name	
				Section 3 MOD.slim	



	Project		
	SLIDE - An Interactive Slope Stability Program		
	Analysis Description		
	Drawn By	Scale 1:2016	Company
Date	2013/07/19, 10:38:07 AM	File Name	Section 3 MOD.slim




	Project			SLIDE - An Interactive Slope Stability Program		
	Analysis Description					
	Drawn By			Scale	1:1998	Company
	Date			2013/07/19, 11:27:19 AM		File Name



	Project		SLIDE - An Interactive Slope Stability Program	
	Analysis Description			
	Drawn By	Scale	1:2546	Company
	Date	2013/07/19, 11:27:19 AM		File Name

**HENDRINA ASH DAM E - ELEVATION vs TIME at 2.33 million m3/annum**





HENDRINA ASH DAM E - ROR vs ELEVATION at 2.33 million m3/annum

